

県道穴笠三次線 舗装修繕工事数量計算総括表

[illegible]

舗装工 数 量 計 算 書

測 点	距 離	舗装工 W=3. 0m以上			舗装工 W=1. 4m～3. 0m			舗装工 W=1. 4m未満		
		幅員	平均	面積	幅員	平均	面積	幅員	平均	面積
I 工区										
県道穴笠三次線										
0. 0					1. 5			白線		
44. 0	44. 0				1. 5	1. 5	66. 0	45 c m : 4. 0m×2本+1. 5m×1本		
50. 0					1. 5			=	9. 5m	
145. 0	95. 0				1. 5	1. 5	142. 5	15 c m : 4. 5m		
								=	4. 5m	
市道十日市47号線										
0. 0					2. 3					
150. 0	150. 0				2. 3	2. 3	345. 0			
市道十日市6号線										
0. 0					2. 0					
4. 0	4. 0				2. 0	2. 0	8. 0			
11. 5	7. 5				2. 0	2. 0	15. 0			
救太才線										
A箇所										
0. 0	0. 0				1. 5					
11. 0	11. 0				1. 5	1. 5	16. 5			
B箇所										
0. 0					1. 2					
13. 0	13. 0				1. 2	1. 2	15. 6			
13. 0	0. 0				2. 8	2. 0	0. 0			
26. 0	13. 0				2. 8	2. 8	36. 4			
小計				0. 0			645. 0			0. 0

舗装工 数 量 計 算 書

測 点	距 離	舗装工 W=3.0m以上			舗装工 W=1.4m～3.0m			舗装工 W=1.4m未満		
		幅員	平均	面積	幅員	平均	面積	幅員	平均	面積
2工区										
大内旭町線										
コミュセン前										
0.0					1.5					
3.0	3.0				1.5	1.5	4.5			
駐車場前										
0.0								1.3		
2.5	2.5							1.3	1.3	3.3
みどりしんきん前										
0.0					2.0					
2.5	2.5				2.0	2.0	5.0			
3工区										
市道三次18号線										
0.0		3.0								
1.6	1.6	3.2	3.1	5.0						
1.6	0.0	2.7	3.0	0.0						
2.7	1.1	2.6	2.7	2.9						
21.6	18.9	3.1	2.9	53.9						
22.0	0.4	2.9	3.0	1.2						
23.4	1.4	3.6	3.3	4.6						
27.7	4.3	3.7	3.7	15.7						
31.2	3.5	3.7	3.7	12.9						
小計				96.2			9.5			3.3

舗装工 数 量 計 算 書

測 点	距 離	舗装工 W=3.0m以上			舗装工 W=1.4m～3.0m			舗装工 W=1.4m未満		
		幅員	平均	面積	幅員	平均	面積	幅員	平均	面積
4工区										
市道胡子坂根線										
0.0					1.5					
4.0	4.0				1.5	1.5	6.0			
市道中原下本谷線										
0.0					1.5					
24.0	24.0				1.5	1.5	36.0			
5工区										
市道三次畠敷線										
コインランドリー前										
0.0					2.0					
13.0	13.0				2.0	2.0	26.0			
エディオン前										
0.0					1.5					
1.5	1.5				1.5	1.5	2.3			
市道宗祐線										
0.0					1.6					
2.0	2.0				1.6	1.6	3.2			
6工区										
市道四拾貫後山線										
A箇所										
0.0								1.0		
3.0	3.0							1.0	1.0	3.0
B箇所										
0.0								1.0		
7.0	7.0							1.0	1.0	7.0
合 計				0.0			73.5			10.0

[illegible]

舗装工 数 量 計 算 書

測 点	距 離	舗装工 W=3.0m以上			舗装工 W=1.4m～3.0m			舗装工 W=1.4m未満		
		幅員	平均	面積	幅員	平均	面積	幅員	平均	面積
7工区										
市道八次20号線										
0.0					1.5					
15.0	15.0				1.5	1.5	22.5			
							10.0			
市道八次135号線										
0.0		4.0								
212.0	212.0	4.0	4.0	848.0						
8工区										
市道宗祐線					白線					
0.0		3.0	1.5	0.0	15 c m : 5.0m					
5.0	5.0	3.0	3.0	15.0	=	5.0m				
市道酒河6号線										
0.0	0.0	4.0								
2.0	2.0	4.0	4.0	8.0						
9工区										
県道三次インター線										
A箇所										
0.0								5.8		
1.2	1.2							5.8	5.8	7.0
B箇所										
0.0								5.8		
0.8	0.8							5.8	5.8	4.6
小計				871.0			32.5			11.6

舗装工 数 量 計 算 書

測 点	距 離	舗装工 W=3.0m以上			舗装工 W=1.4m～3.0m			舗装工 W=1.4m未満		
		幅員	平均	面積	幅員	平均	面積	幅員	平均	面積
10工区										
市道神杉11号線										
0.0		3.0								
53.0	53.0	3.0	3.0	159.0						
市道山家線										
0.0		6.0								
16.0	16.0	6.0	6.0	96.0						
11工区										
県道青河江田川之内線										
A箇所										
0.0		2.4								
3.0	3.0	4.1	3.3	9.8						
B箇所										
0.0					1.5	0.8	0.0			
1.0	1.0				2.0	1.8	1.8			
C箇所										
0.0					1.8					
3.5	3.5				1.8	1.8	6.3			
小計				264.8			8.1			0.0

舗装工 数 量 計 算 書

測 点	距 離	舗装工 W=3.0m以上			舗装工 W=1.4m～3.0m			舗装工 W=1.4m未満		
		幅員	平均	面積	幅員	平均	面積	幅員	平均	面積
12工区										
市道志幸上田線										
平地部										
0.0										
10.0	10.0	2.3	1.2	11.5						
26.0	16.0	6.0	4.2	66.4						
バス停										
0.0		4.0								
15.0	15.0	0.0	2.0	30.0						