

数量計算書

費目	工種	種別	細別	規格	単位	数量	摘要
土工							
	床掘			BH0.1	m3	16.1	
	埋戻			BH0.1	m3	21.3	
	盛土			BH0.1	m3	23.3	
	購入土				m3	33.5	
	盛土法面整形				m2	48.4	
法面保護工							
	盛土法面保護工			ワラ芝	m2	48.4	
	張コンクリート工			18-8-40	箇所	1.0	
擁壁工							
	小型重力式擁壁			S GW-2 2 18-8-40	m3	6.0	
	鉄筋工			差筋 D13 SD295	kg	5.8	0.995kg/m*0.2*29=5.8kg
	削孔工			ハンマドリル	孔	29.0	
	縁石積工			控300	m2	1.0	
水路工							
	水路敷設工	新設		角フリームKF300	m	22.0	
	水路敷設工	再利用設置		フリーム300	m	4.0	
	水路撤去工	再利用撤去		フリーム300	m	2.0	
	接合用パット			KF300	個	10.0	
上水道布設替工 ドレーン管布設替							
	塩ビ管布設工			H1VP φ50	m	2.5	
	T S継手工			φ50	口	2.0	
	管切断工			φ50	口	2.0	
	塩ビ管			H1VP φ50 直管 L=4000	本	1.0	
	塩ビ管			H1VP φ50 90度エルボ	個	1.0	
	砂基礎工			ダスト	m3	0.1	
雑工							
	アスカープ				m	17.0	
仮設工							
	単管傾斜足場				掛m2	37.2	
安全費							
	交通誘導員		交通誘導員B		人	9	

(No.)

計算書

[illegible]

(No.)

計 第 2 表

土工 2

計算書

測点	距離	盛土			盛土法面整形			植生工			備考
		断面	平均	体積	法長	平均	面積	法長	平均	面積	
擁壁工											
ST.0.0		0.5			2.9			2.9			
ST.2.0	2.0	1.7	1.10	2.2	3.1	3.00	6.0	3.1	3.00	6.0	
ST.4.0	2.0	1.7	1.70	3.4	3.1	3.10	6.2	3.1	3.10	6.2	
ST.8.0	4.0	1.5	1.60	6.4	3.0	3.05	12.2	3.0	3.05	12.2	
ST.14.0	6.0	1.5	1.50	9.0	3.0	3.00	18.0	3.0	3.00	18.0	
ST.15.0	1.0	1.5	1.50	1.5	3.0	3.00	3.0	3.0	3.00	3.0	
ST.16.0	1.0	0.0	0.75	0.8	3.0	3.00	3.0	3.0	3.00	3.0	
合 計	16.0			23.3			48.4			48.4	

(No.)

計 第 3 表	
1	2
3	4
5	6
7	8
9	10
11	12
13	14
15	16
17	18
19	20
21	22
23	24
25	26
27	28
29	30
31	32
33	34
35	36
37	38
39	40
41	42
43	44
45	46
47	48
49	50
51	52
53	54
55	56
57	58
59	60
61	62
63	64
65	66
67	68
69	70
71	72
73	74
75	76
77	78
79	80
81	82
83	84
85	86
87	88
89	90
91	92
93	94
95	96
97	98
99	100

擁壁工

計算書

測点	距離	コンクリート			型枠			練石積			備考
		断面	平均	体積	長さ	平均	面積	法長	平均	面積	
ST.0.0		0.01			0.41						
ST.2.0	2.0	0.43	0.22	0.40	2.24	1.33	2.70				
ST.4.0	2.0	0.43	0.43	0.90	2.24	2.24	4.50				
ST.8.0	4.0	0.43	0.43	1.70	2.24	2.24	9.00				
ST.14.0	6.0	0.43	0.43	2.60	2.24	2.24	13.40				
ST.15.0	1.0	0.43	0.43	0.40	2.24	2.24	2.20				
ST.15.0								1.02			
ST.16.0	1.0							1.02	1.02	1.0	
合計	16.0			6.0			31.8			1.0	

(No.)

計 第 4 表

水路工

計算書

[illegible]

(No.)

計 第 5 表

上水道布設替工

計算書

測点	距離	ドレーン布設替 HIVP φ 50			ドレーン布設替 HIVP φ 50 90度エルボ			砂基礎工 ダスト			備考
				延長			個数			体積	
ST.8.0				2.5			1.0			0.1	
								0.2*0.2*2.5=0.1			
合 計	0.0			2.5			1.0			0.1	

(No.)

計 第 6 表

仮設工

計算書

[illegible]